

CERTIFICATE OF COMPLIANCE

SEISMIC DESIGN OF NONSTRUCTURAL COMPONENTS AND SYSTEMS



Certification No.

VMA-52604-03C (Revision 0)

Expiration Date: 12/31/2028

Certification Parameters:

The nonstructural products (mechanical and/or electrical components) listed on this certificate are **CERTIFIED¹** FOR SEISMIC APPLICATIONS in accordance with the following building code² releases.

IBC 2018, 2015, 2012, 2009

The following model designations, options, and accessories are included in this certification. Reference report number VMA-52604-01 as issued by The VMC Group for a complete list of certified models, included accessories/options, and certified installation methods.

**JC Residential & Light Commercial LLC; Packaged Air Conditioners
Omni Premier; 25-80 Ton**

The above referenced equipment is **APPROVED** for seismic application when properly installed³, used as intended, and contains a Seismic Certification Label referencing this Certificate of Compliance⁴. As limited by the tabulated values, below grade, grade, and roof-level installations, installations in essential facilities, for life safety applications, and/or of equipment containing hazardous contents are permitted and included in this certification with an Equipment Importance Factor assigned as $I_p=1.5$. The equipment is qualified by successful seismic shake table testing at the nationally recognized University of California Berkeley Pacific Earthquake Engineering Research Center and CERL (US Army Corp. of Engineers) Laboratory under the witness of the ISO Accredited Product Certification Agency, the VMC Group.

Certified Seismic Design Levels			
Certified IBC	Importance $I_p \leq 1.5$ Soil Classes A-E Risk Categories I-IV Design Categories A-F	$z/h \leq 1.0$	$z/h = 0.0$
		$S_{DS} \leq 1.400 \text{ g}$	$S_{DS} \leq 1.400 \text{ g}$

Certified Seismic Installation Methods	
Directly To Floor	Directly To Rigid Curb/Rail



CERTIFICATE OF COMPLIANCE

SEISMIC DESIGN OF NONSTRUCTURAL COMPONENTS AND SYSTEMS

Certified Product Table:

Model	Unit Size (Tonnage)	Unit No.	Weight [lbs]	Length [in.]	Width [in.]	Height [in.]
Premier (Gryphon)	25	1	6899	264	96	55
		17	9975	473		
		19	12465	550		
	30	1	6899	264		70
		19	12465	550		
	40	28	8133	297		
		46	14069	580		
	50	28	8133	297		
		42	12971	538		
		46	14069	580		
	60	55	7699	299	113	80
		84	17541	633		
	70	97	9584	365		
		126	20190	718		
	80	97	9700	365		
		126	22700	740		

Type	S _{DS} (z/h=0)	S _{DS} (z/h=1)	A _{Flex-H}	A _{Rig-H}	A _{Flex-V}	A _{Rig-V}	F _p /W _p
AC156	1.40	1.40	2.24	1.68	0.94	0.38	1.05

This certification includes the Nexus Premier Air Handler Units and included factory supplied options. This certification only covers accessories and options as listed in the reference report issued by The VMC Group. The AHU shall be installed per the manufacturer supplied seismic installation instructions. For a list of certified configurations and options please directly contact the manufacturer. This certification excludes all non-factory supplied accessories and options, including but not limited to isolation/restraint devices, other electrical/mechanical components and all connections for electrical, fuel, heating or cooling fluid, or other pipe/conduit connections and configurations not detailed in the above charts. Flexibility in the connections must be maintained as to not transmit load into the equipment. Design specials are outside the scope of this certification.



VMA-52604-03C (Revision 0)
Issue Date: December 15, 2025
Revision Date: December 15, 2025
Expiration Date: December 31, 2028



CERTIFICATE OF COMPLIANCE

SEISMIC DESIGN OF NONSTRUCTURAL COMPONENTS AND SYSTEMS

Notes & Comments:

1. All equipment listed herein successfully passed the seismic acceptance criteria for shake testing non-structural components and systems as set forth in the ICC AC-156. The Test Response Spectrum (TRS) enveloped the Required Response Spectrum (RRS) for all units tested. The tested units were representative sample(s) of a contingent of models and all remained captive and structurally sound after the seismic shake simulation. The units also remained functionally operational after the simulation testing as functional testing was completed by the equipment manufacturer before and after the seismic simulations. Although a seismic qualified unit inherently contains some wind resisting capacity, that capacity is undetermined and is excluded from this certification. Snow/Ice loads have been neglected and thus limit the unit to be installed both indoors (covered by an independent protective structure) and out of doors (exposed to accumulating snow/ice) for ground snow loads no greater than 30 psf for all applications.
2. The following building codes are addressed under this certification:
 - IBC 2018 referencing ASCE7-16 and ICC-ES AC-156
 - IBC 2015 referencing ASCE7-10 and ICC-ES AC-156
 - IBC 2012 referencing ASCE7-10 and ICC-ES AC-156
 - IBC 2009 referencing ASCE7-05 and ICC-ES AC-156
3. Refer to the manufacturer supplied installation drawings for anchor requirements and mounting considerations for seismic applications. Required anchor locations, size, style, and load capacities (tension and shear) may be specified on the installation drawings or specified by a 3rd party. Mounting requirement details such as anchor brand, type, embedment depth, edge spacing, anchor-to-anchor spacing, concrete strength, special inspection, wall design, and attachment to non-building structures must be outlined and approved by the Engineer of Record for the project or building. Structural walls, structural floors, and housekeeping pads must also be seismically designed and approved by the project or building Structural Engineer of Record to withstand the seismic anchor loads as defined on the installation drawings. The installing contractor is responsible for ensuring the proper installation of all anchors and mounting hardware.
4. For this certificate and certification to remain valid, this certificate must correspond to the "Seismic Certification Label" found affixed to the unit by the factory. The label ensures the manufacturer built the unit in conformance to the IBC seismic design criteria set forth by the Certified Seismic Qualification Agency, the VMC Group, and meets the seismic design levels claimed by this certificate.
5. Mechanical, Electrical, and Plumbing connections to the equipment must be flexibly attached as to not transfer load through the connection. The structural integrity of any conduit, cable trays, piping, ductwork and/or flexible connections is the responsibility of others. This certification makes no statements of compliance in regards to NEMA, IP, UL, CSA, or other relevant standards after a seismic event. For compliance to other relevant standards, please contact the manufacturer.
6. This certificate applies to units manufactured at:
 - 5005 Interstate Drive, Norman, OK, 73069
7. This certification follows the VMC Group's ISO-17065 Scheme.



John P. Giuliano, PE
President, VMC Group



VMA-52604-03C (Revision 0)
Issue Date: December 15, 2025
Revision Date: December 15, 2025
Expiration Date: December 31, 2028

